## CHOUTPALLY HANUMANTH REDDY LIFT IRRIGATION SCHEME



#### Preamble:

This Lift Irrigation Scheme is proposed on Shetpally tank which is fed by Distributory D4 of Sri Ramasagar Project Laxmi canal. The project is taken up to provide irrigation facility to an ayacut of 11,625 Acres(5802 Acres of Wet & 5823 Acres of dry) in 18 villages of Kammarpally & Morthad Mandals in Nizamabad District by lifting 180 cusecs of water.

## Location:

| Source   | Shetpally Tank (D4 of Laxmi canal |
|----------|-----------------------------------|
|          | of Sriramsagar Project)           |
| Village  | Shetpally                         |
| Mandal   | Morthad                           |
| District | Nizambad                          |

# Lift Details:

| Cost of Project    | Rs.75.14 Crores   |
|--------------------|---|
| No. of Lifts       | 3   |
| Lift               | 72.90M.<br><b>Stage-I –</b><br>(31.75 Mts, 46.20 Mts, 72.90 Mts &<br>49.80 Mts)<br><b>Stage - II(a)-</b> 29.15 Mts<br><b>Stage - II(b)-</b> 47.55 Mts |
| No. of Pumps       | 6 Nos. (4.395 MW)   |
| Make of Pumps      | ABB   |
| Type of Pumps used | V.T.Pump  |
| Pump Capacity      | 1 No x 4179 Cum/Hrs<br>2 Nos x 2853 Cum/Hrs<br>1 No x 2038 Cum/Hrs<br>2 Nos x 3618 Cum/Hrs<br>1 No x 2089 Cum/Hrs                                     |

|                               | 1 No x 1733 Cum/Hrs |
|-------------------------------|---------------------|
| Quantum of Water to be Lifted | 1.00 TMC            |
| Total Power Requirement       | 5.14 MW             |
| Length of Pressure Main       | 56.45 KM            |
| Total Length of Scheme        | 27.22 KM            |
| Discharge                     | 180 cusecs          |

### Irrigation Potential:

This Project was constructed to irrigate an ayacut of 11,625 Acres benefiting in Wyra, Kammarpally & Morthad mandals of Nizambad district.

### Status of Project:

Operation & Maintenance in Progress.

## Schematic Diagram:

